

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-063-20933-00-00
Spot: NENENE Sec/Twnshp/Rge: 17-11S-31W
4950 feet from S Section Line, 330 feet from E Section Line
Lease Name: ENGEL A Well #: 1
County: GOVE Total Vertical Depth: 4710 feet

Operator License No.: 8541
Op Name: PETEX, INC.
Address: 4175 S FR 193
ROGERSVILLE, MO 65742

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| PROD | 4.5 | 4737 | 0 | 180 SX |
| SURF | 8.625 | 217 | 0 | 165 SX |

153.08

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/09/2008 2:00 PM
Plug Co. License No.: 6454 Plug Co. Name: CHEYENNE WELL SERVICE, INC.
Proposal Rcvd. from: LARRY CHILDRESS Company: PETEX, INC. Phone: (417) 887-1225

Proposed Plugging Method: Ordered 360 sxs 60/40 pozmix - 4% gel - 500# hulls - 16 sxs gel spacer.
Top down plug.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/09/2008 3:30 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface pipe set at 217' w/165 sxs cement.
4 1/2" production casing set at 4737' w/180 sxs cement.
Multistage collar set at 2501'. Cement amount not reported.
Connected to 4 1/2" production casing - pumped 100# hulls with water.
Pumped 60 sxs cement mixed with 400# hulls - 16 sxs gel spacer followed with 80 sxs cement.
Max. P.S.I. 1000#. S.I.P. 800#.
Connected to 8 5/8" surface pipe - pumped 60 sxs cement.
Annulus on vacuum - pumped 60 sxs cement.
Max. P.S.I. 200#. S.I.P. 0#.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 4668 | 4677 | | |
| 4648 | 4652 | | |
| 4605 | 4616 | | |
| 4199 | 4201 | | |

INVOICED
DATE 8-11-08
INV. NO. 2009060216

RECEIVED
KANSAS CORPORATION COMMISSION
JUL 25 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY-TICKET #31550.

Plugged through: CSG

District: 04

Signed Darrel Dipman
(TECHNICIAN) CM


JUL 10 2008

Handwritten initials

REPLACEMENT CARD

PETEX, INC. #1 'A' ENGEL 17-11-31W
 DT 2 BOX 553 ROGERVILLE, MO 65742 NE NE NE
 COUNTY BLUE GOOSE DRILLING CTY GOVE

GEOL SAM HOUSTON FIELD WC(CAMPUS EAST DISC)



ELV 3018 KB SPD 7/2/85 CARD ISSUED 9/26/85 IP P 26 BO & 20 BWPD
 3011 GL DRLG COMP 7/12/85 LKC 4199-4201
 API 15-063-20,933

| SMP | Tops | Depth/Datum | |
|------------|------|-------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| | | | 8 5/8 " 217 / 165 SX, 4 1/2 " 4737 / 180 SX, MULTI STAGE COLLAR AT 2501 NO CORES |
| HEEB | | 4002- 984 | |
| LANS | | 4044-1026 | DST (1) 4102-4135 (LKC) / 60-60-60-60, REC 5' O & WCM, 115' MW (CHL 58,000 PPM), SIP 876-766#, FP 44-88 / 122-200#, HP 2266-2177# |
| STARK | | 4266-1248 | |
| BKC | | 4331-1313 | DST (2) 4173-4240 (LKC) / 60-60-60-60, REC 5' OIL, 175' G & MCO, SIP 1218-1218#, FP 33-66 / 77-88#, HP 2177-2100# |
| MAPM | | 4367-1349 | |
| PAW | | 4454-1436 | DST (3) 4236-4305 (LKC) / 60-60-60-60, REC 80' SLI OCM (3% OIL), SIP 1163-853#, FP 44-66 / 77-88#, HP 2244-2144# |
| FT SC | | 4522-1504 | |
| CHER | | 4548-1530 | DST (4) 4440-4515 (PAW) / 45-45-45-45, REC 10' M, W / TR OIL, SIP 50-60#, FP 50-50 / 60-60#, HP 2306-2214# |
| JOHNSON ZN | | 4592-1574 | |
| MISS | | 4635-1617 | DST (5) 4564-4632 (JOHNSON ZN) / 60-60-60-60, REC 390' G & MCO, SIP 835-763#, FP 60-131 / 182-182#, HP 2387-2295# |
| RTD | | 4710-1692 | DST (6) 4649-4675 (MISS) / 45-45-45-45, REC 60' OIL, 150' M & GCO, 60' O & MCW, 240' MW (CHL 35,000 PPM), SIP 1040- INFO RELEASED: 1/1/87 - WAS OIL WELL - TIGHT HOLE |

COPYRIGHT 1977
 INDEPENDENT OIL & GAS PRODUCE CO.
 WICHITA, KANSAS

(over)

PETEX, INC. #1 'A' ENGEL 17-11-31W
 NE NE NE

845#, FP 121-182 / 253-253#, HP 2510-2448#
 MICT - CO, PF (MISS) 4668-4677, W / 4 SPF, AC 250 GAL (15% INS), SWB DWN, NON-COMMERCIAL, PF (MISS) 4648-4652, W / 2 SPF, AC 250 GAL (15% INS), SWB DWN, NON-COMMERCIAL, PF (JOHNSON ZN) 4605-4616, W / 2 SPF, AC 500 GAL (7.5% INS), FRAC 13,000# SD & CROSS-LINK GEL (ARIT MA), SWB DWN, NON-COMMERCIAL, PF (LKC H) 4199-4201, W / 2 SPF, AC 2000 GAL (15% SGA), SWB DWN, SO, SET 2 BR TBG AT 4601.45. POP, P 26 BO & 20 BWPD (GR 35%), 8/16/85