

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-01606-00-02 15-195-01006-00-03
Spot: SWSWSE Sec/Twnshp/Rge: 4-12S-22W
330 feet from S Section Line, 2310 feet from E Section Line
Lease Name: EHR FARMS INC Well #: 3
County: TREGO Total Vertical Depth: 4135 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: 8100 E 22ND ST N # 700 BOX 783188
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4114	0	w/250 sxs cmt
SURF	10.75	238	0	w/unknown sxs cmt

134.39

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/16/2008 9:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: TOM ATKINS Company: RITCHIE EXPLORATION, INC. Phone: (785) 216-0155

Proposed Plugging Method: Ordered 415 sxs 60/40 pozmix - 4% gel - 700# hulls.
Emergency plug with rig over the hole.
P.C. at 1844' cwc w/500 sxs.
Operator elected all cement plug.
Junk in the hole at 2190'. Bad casing. High fluids.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/16/2008 2:45 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Express Well Service RIH with tubing to 2167'. Allied rigged to tubing - pumped 75 sxs 60/40 pozmix - 4% gel.
Pulled tubing to 1850'. Allied rigged to tubing - pumped 260 sxs 60/40 pozmix - 4% gel with 400# hulls mixed in.
Pulled tubing to 1000'. Allied rigged to tubing - pumped 75 sxs cement with 300# hulls to circulate cement to pit.
Pulled tubing - topped off 4 1/2" casing with 5 sxs.
Rigged to 10 3/4" casing - instant pressure on backside.

Perfs:

Top	Bot	Thru	Comments
3640	4014		

INVOICED

DATE 8-11-08
INV. NO. 2009060221

RECEIVED
KANSAS CORPORATION COMMISSION
JUL 25 2008

Remarks: ALLIED CEMENTING COMPANY-TICKET #71733.

Plugged through: TBG

District: 04

Signed [Signature]
(TECHNICIAN)

CM

Form CP-2/3

JUL 21 2008

[Handwritten initials]

