

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-24678-00-00

Spot: SWNESW

Sec/Twnshp/Rge: 20-11S-19W

KCC PKT
GPS D

1670 ~~1650~~ feet from S Section Line, ~~3630~~ feet from E Section Line

Lease Name: WILES

3771

Well #: 2

County: ELLIS

Total Vertical Depth: 3518 feet

Operator License No.: 5184

Op Name: SHIELDS OIL PRODUCERS INC

Address: 326 N MAIN
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3513	0	150 SX
SURF	8.625	224	0	190 SX

114.34

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 07/16/2008 8:30 AM

Plug Co. License No.: 5184

Plug Co. Name: SHIELDS OIL PRODUCERS INC

Proposal Rcvd. from: MICHAEL A. MCGLOCKLIN Company: SHIELDS OIL PRODUCERS INC

Phone: (785) 483-3141

Proposed Plugging Method: Ordered 400 sxs 60/40 pozmix - 4% gel - 500# hulls.
Port collar at 1353' - circulate cement.

Plugging Proposal Received By: BRUCE BASYE

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 07/16/2008 2:30 PM

KCC Agent: MARVIN MILLS

Actual Plugging Report:

Perfs:

Ran tubing in to 3400' - pumped 100 sxs 60/40 pozmix - 4% gel with 200# hulls with good circulation of fluid.
Pulled tubing to 2300' - pumped 100 sxs cement with 200# hulls.
Pulled tubing to 1300' - pumped 120 sxs cement with 100# hulls with good circulation of cement.
Pulled tubing out - tied onto backside - pumped 15 sxs cement.
Max. P.S.I. 200#. Shut in.
Topped off 5 1/2" with 35 sxs. Hole full.

INVOICED

DATE 8-11-08
INV. NO. 2009060225

RECEIVED
KANSAS CORPORATION COMMISSION

JUL 25 2008


CONSERVATION DIVISION
WICHITA, KS

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #2459.

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

CM

Form CP-2/3

JUL 18 2008



STATE KANS COUNTY ELLIS
FIELD ZERFAS (LANSING/ARBUCKLE)
OPER SHIELDS OIL PRODUCERS
WELL 2 WIRES
API 15-051-24678-0000
SPUD 08/25/1990
DTD 3518 LTD FTD PENN

20-11S-19W
SW NE SW
1650FSL 3630FEL SEC
WELL CLASS DO
STATUS OIL
COMP 09/14/1990
PRTD



LOC 11 MI NE ELLIS, KS

Petroleum Information

IPP 50 BOPD
PROD ZONE: LANSING 3513-3518 OPENHOLE

EL: 1965 KB 1960 GR

CSGS: 8 5/8 @ 224 W/ 190 SACKS
5 1/2 @ 3513 W/ 150 SACKS
DRLG COMP 9/2/90 RIG REL 9/2/90

SPL TOPS:
STONE CORL AN 1312 +653
BSE STN CORL AN 1355 +610
TOPEKA 2947 -982
HEEBNER 3164 -1199
LANSING 3208 -1243
TD 3518 -1553

DSTS: DST 1 3231-3252 LANSING
REC 160 FT GAS 80 FT HOCH
IFP 40 FFP 48
IFP 59 FFP 65 TIMES NOT RPTD
ISIP 350 FSIP 358
DST 2 3268-3303 LANSING
REC 190 FT HOCH 70 FT GAS
INIT OP 30M IFP 57 FFP 73
FINAL OP 30M IFP 89 FFP 105
ISIP 504 30M FSIP 512 45M
DST 3 3372-3388 LANSING
REC 20 FT MUD W/SPKS OIL

NO LOGS RPTD

KS 11-100290

CONTINUED

Copyright 1990 Petroleum Information Corporation