

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

Operator License No.: 33097

Op Name: SOUTHERN STAR CENTRAL GAS PIPE

Address: 4700 HWY 56
OWENSBORO, KY 42301

API Well Number: 15-001-01893-00-01
Spot: SWNW Sec/Twnshp/Rge: 2-25S-17E
3821 feet from S Section Line, 4764 feet from E Section Line
Lease Name: PIQUA GAS STORAGE Well #: 7
County: ALLEN Total Vertical Depth: 904 feet

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.187	868		160 SX
SURF	8.625	10		<u>35</u>

Well Type: GSW

UIC Docket No:

Date/Time to Plug: 07/07/2008 8:00 AM

Plug Co. License No.: 6372

Plug Co. Name: SPLANE PULLING AND ROUSTABOUT SERVICE, INC.

Proposal Revd. from: BERNIE ROCKERS

Company: SOUTHERN STAR CENTRAL GAS P Phone: (785) 448-4816

Proposed Plugging Method: CLEAN OUT TO T.D. SET RETAINER AND PLUG SOLID WITH TUBING FROM TOTAL DEPTH TO SURFACE WITH CLASS A CEMENT. CUT CASING 4' BELOW SURFACE. BACKFILL AND RECLAIM SITE.

Plugging Proposal Received By: CLAYTON TITEL

WitnessType: NONE

Date/Time Plugging Completed: 07/07/2008 5:00 PM

KCC Agent: CLAYTON TITEL

Actual Plugging Report:

Perfs:

THIS WELL CONSISTED OF 5.187 CASING TO 868' THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. 3 1/2" TUBING ON A PACKER WAS STUCK IN THE WELL FROM SURFACE TO 854'. THE 3 1/2" TUBING WAS PERFORATED FROM 843' TO 844'. 1" PIPE WAS RAN INTO THE WELL TO 904'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE WELL AT SURFACE BOTH INSIDE AND OUTSIDE THE 3 1/2" TUBING. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE. THE WELL WAS THEN SQUEEZED AND SHUT IN.

RECEIVED
KCC DISTRICT #3

JUL 16 2008 CPT

CHANUTE, KS

RECEIVED
KANSAS CORPORATION COMMISSION
JUL 23 2008
CONSERVATION DIVISION
WICHITA, KS

INVOICED
DATE 8-11-08
INV. NO. 2009060226

Remarks:

Plugged through: TBG

District: 03

Signed Clayton P. Titel
(TECHNICIAN)