

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-207-19429-00-01  
Spot: SESENE Sec/Twnshp/Rge: 3-25S-17E  
3042 feet from S Section Line, 412 feet from E Section Line  
Lease Name: PIQUA GAS STORAGE Well #: 14  
County: WOODSON Total Vertical Depth: 906 feet

Operator License No.: 33097  
Op Name: SOUTHERN STAR CENTRAL GAS PIPE  
Address: 4700 HWY 56  
OWENSBORO, KY 42301

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.187	885		169 SX
SURF	8.625	9		

35

Well Type: GSW UIC Docket No: Date/Time to Plug: 07/15/2008 1:00 PM  
Plug Co. License No.: 6372 Plug Co. Name: SPLANE PULLING AND ROUSTABOUT SERVICE, INC.  
Proposal Rcvd. from: BERNIE ROCKERS Company: SOUTHERN STAR CENTRAL GAS P Phone: (785) 448-4816

Proposed Plugging Method: CLEAN OUT TO T.D. SET RETAINER AND PLUG SOLID WITH TUBING FROM TOTAL DEPTH TO SURFACE WITH CLASS A CEMENT. CUT CASING 4' BELOW SURFACE. BACKFILL AND RECLAIM SITE.

Plugging Proposal Received By: CLAYTON TITEL WitnessType: PARTIAL  
Date/Time Plugging Completed: 07/15/2008 5:00 PM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

Perfs:

THIS WELL CONSISTED OF 5.187' TO 885' THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. 1" PIPE WAS RAN INTO THE 5.187" CASING TO T.D.. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE CASING AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE. THE WELL WAS THEN SQUEEZED AND SHUT IN.

RECEIVED  
KCC DISTRICT #3

JUL 16 2008 CPT  
CHANUTE, KS

RECEIVED  
KANSAS CORPORATION COMMISSION

JUL 23 2008

CONSERVATION DIVISION  
WICHITA, KS

INVOICED

DATE 8-11-08  
INV. NO. 2007060226

Remarks:

Plugged through: TBG

District: 03

Signed Clayton P. Titel  
(TECHNICIAN)

PS