

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-02123-00-00
Spot: N2SWSE Sec/Twnshp/Rge: 7-11S-17W
990 feet from S Section Line, 1980 feet from E Section Line
Lease Name: STEIN Well #: 3
County: ELLIS Total Vertical Depth: 3384 feet

Operator License No.: 33699
Op Name: T-N-T ENGINEERING, INC.
Address: 3711 MAPLEWOOD STE 201
WICHITA FALLS, TX 76308

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|---------------------------------|
| COND | 16 | 40 | 0 | |
| PROD | 7 | 3382 | 0 | w/unknown sxs cmt <u>109.98</u> |
| SURF | 10.75 | 1120 | 0 | w/unknown sxs cmt |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/16/2008 1:00 PM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: RANDY WEIGEL Company: T-N-T ENGINEERING, INC. Phone: (785) 737-3736

Proposed Plugging Method: Ordered 400 sxs 60/40 pozmix - 4% gel - 3% c.c. on side - 500# hulls - 25 sxs gel spacer.
Casing leak. Fluid level 600'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/16/2008 4:15 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perforated two holes each at 1650' - 1125'; 550 - 150'.
Ran tubing to 3200'. Allied pumped 25 sxs gel spacer, followed with 75 sxs 60/40 pozmix - 4% gel with 3% cc and 300# hulls.
Pulled tubing to 1650'. Allied pumped 60 sxs 60/40 pozmix - 4% gel with 100# hulls.
Pulled tubing to 1125'. Allied pumped 225 sxs 60/40 pozmix - 4% gel - circulated cement out 16" - 10 3/4" - 7".
PTOH. Topped off with 40 sxs cement - casing full.

Perfs:

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed Richard Williams
(TECHNICIAN) CM

INVOICED
DATE 8-11-08
INV. NO. 2009060227

RECEIVED
KANSAS CORPORATION COMMISSION

JUL 25 2008

CONSERVATION DIVISION
WICHITA, KS

JUL 18 2008

PT

DICKEY OIL CO #3 STEIN 7-11-17W
 CN2 SW SE

Contr. _____ ELLIS County
 E 1865 Comm 1-26-40 Comp. 2-18-40 IP 3000 BOFD

| Tops | Depth | Datum | Casing |
|------|-------|-------|-----------|
| | | | 15" 61 |
| TOP | 2825 | | 7" 3381 |
| DOUG | 3035 | | |
| LANS | 3086 | | |
| | | | 2900' OIH |
| CONG | 3320 | | |
| | | | |
| SIMP | 3363 | | |
| ARB | 3380 | | |
| | | | |
| TD | 3384 | | |

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

| | | |
|--|--|--|
| | | |
| | | |
| | | |