

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-22782-00-00
Spot: W2NWNE Sec/Twnshp/Rge: 24-8S-18W
4620 feet from S Section Line, 2310 feet from E Section Line
Lease Name: THOMAS A Well #: 2
County: ROOKS Total Vertical Depth: 3423 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 S MAIN STE 200
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3403	0	w/150 sxs cmt
SURF	8.625	261	0	w/160 sxs cmt <u>111.25</u>

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/23/2008 10:00 AM
Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.
Proposal Rcvd. from: FRANK BIEKER Company: TRANS PACIFIC OIL CORPORATIO Phone: (785) 658-7258

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 500# hulls
Bridge plug set at 3330'. Out of hole at 1426'.

Plugging Proposal Received By: BRUCE BASYE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/23/2008 11:30 AM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 1400' - spotted 60 sxs 60/40 pozmix - 4% gel with 100# hulls.
Pulled tubing to 700' - pumped 60 sxs 60/40 pozmix - 4% gel with 100# hulls - had circulation to surface.
Pulled all tubing and topped off 4 1/2" casing with 10 sxs 60/40 pozmix - 4% gel.
Hooked onto backside and pumped 15 sxs 60/40 pozmix - 4% gel.
S.I.P. 200#.

Perfs:

INVOICED
DATE 8-11-08
INV. NO. 2009060228

RECEIVED
KANSAS CORPORATION COMMISSION
AUG 01 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: QUALITY OILWELL CEMENTING-TICKET #2130.


Plugged through: TBG

District: 04

Signed Pat Bedore
(TECHNICIAN) CM

PBT

SHARP ENGINEERING
 OIL OPERATIONS
 708 ONE MAIN PLACE #2 THOMAS A 24-8-18W
 WICHITA, KS. 67202 C W/2 NW NE
 CONTR MURFIN DRILLING CTY ROOKS
 GEOL GARY SHARP FIELD DOPITA
 ELV 1976 KB SPD 10/31/85 CARD ISSUED 4/3/86 IP P 27 BOPD, NW
 1977 GL DRLG COMP 11/6/85 ARB OH 3403-3420



LOG	Tops	Depth/Datum
ANH	1312	664
B ANH	1349	627
TOP	2891	915
HEEB	3103	1127
TOR	3125	1149
LANS	3144	1168
BKC	3366	1390
ARB	3402	1426
LTD	3414	1438
RTD	3420	1444

API 15-163-22,782
 8 5 8 " 261 160SX, 4 1 2 " 3403 150SX
 DST (1) 3282-3354 (LKC) 30-45-15-0. REC 5' M. SIP 283-0#.
 FP 49-49 49-49#
 DST (2) 3347-3370 (LKC) 30-45-10-0. REC 1' M. PRESSURES
 NA
 DST (3) 3406-3420 (ARB) TIMES NA. REC 60' OIL SPKD M. SIP
 732-732#, FP 20-40 40-60#, HP 1753-1734#
 MICT - CO. (ARB OH), AC 1000 GAL (15% SD-FE). SWB DWN.
 RE-AC 2500 GAL (15% SGA), SO. SET 2 3 8 " TBG AT 3398.
 POP, P 27 BOPD, NW (GR 28'), 12 16.85

COPYRIGHT 1985
 INDEPENDENT OIL & GAS SERVICE, INC.
 WICHITA, KANSAS