

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-063-21533-00-00
Spot: NESESW Sec/Twnshp/Rge: 29-14S-30W
977 feet from S Section Line, 3153 feet from E Section Line
Lease Name: MCKANDER Well #: 1
County: GOVE Total Vertical Depth: 4480 feet

Operator License No.: 6170
Op Name: GLOBE OPERATING, INC.
Address: PO BOX 12
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
DVT		2149		
PROD	5.5	4473	0	150 SX
SURF	8.625	220	0	160 SX

145.60

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/05/2008 10:00 AM
Plug Co. License No.: 32970 Plug Co. Name: H-D OILFIELD SERVICE, INC.
Proposal Rcvd. from: RICHARD STALCUP Company: GLOBE OPERATING, INC. Phone: (620) 793-2891

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 4% gel - 23 sxs gel - 300# hulls.
Plug through casing.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/05/2008 11:30 AM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface pipe set at 220' w/160 sxs cement.
5 1/2" production casing set at 4473' w/150 sxs cement.
DV tool at 2149' w/450 sxs.
Connected to 5 1/2" production casing - pumped 50 sxs cement with 300# hulls - 18 sxs gel - 40 sxs cement - 4 sxs gel and 160 sxs cement.
Max. P.S.I. 300#. S.I.P. 0#.
Casing on vacuum. Cement visible in 8 5/8" surface casing.
5 1/2" casing to be topped when trucks available.
06/26/2008 - Topped off with three yards neat cement.

Perfs:

Top	Bot	Thru	Comments
4293	4303		
4062	4066		
4013	4020		

INVOICED
DATE 8-6-08
INV. NO. 2009060197

RECEIVED
KANSAS CORPORATION COMMISSION
JUL 25 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY-TICKET #31988.

Plugged through: CSG

District: 04

Signed Darrel Dipman
(TECHNICIAN) CM

JUL 15 2008

PAT

GLOBE OPERATING
GREAT BEND KS 67530-0012

29-14S-30W
NE SE SW

1 MCKANDER

site: 10-1/2 S & 9-1/2 W OF GOVE KS	co: GOVE	API 15-063-21533
contr: DISCOVERY DRILLING # 1	field: BUTTERFIELD-OVERLAND	
opd: JAMES C MUSGROVE	SE EXT (1/4 N)	
dr date 04/19/99	sp date 04/28/99	drig comp 05/06/99
	card issued 08/16/99	last revised 08/16/99

ELV: 2722 KB, 2714 GL
tops depth/ datum
RTD 4480 -1758
NO TOPS RPTD

IP status:
OIL, MARM, INTV NA, 06/01/99
CSG: 8-5/8" 220.81 (ALT 2), PROD CSG NA, MULTI
STAGE COLLAR AT 2149 / 450 SX
COMMENT: MIRT 4/27/99
TRGT ZN: LKC (OIL), PTD 4450 (MISS), MICT - CO, PF
(MYR STA) INTV NA, SO, POP, OIL WELL (POTENTIAL
NOT RPTD), 6/1/99 - NO OTHER INFO AVAILABLE -
TEMP COMP 8/16/99

COPYRIGHT 1999
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS