

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-21350-00-00  
Spot: NESEWSE Sec/Twnshp/Rge: 36-15S-13W  
1650 feet from S Section Line, 1650 feet from E Section Line  
Lease Name: SELLENS B Well #: 3  
County: RUSSELL Total Vertical Depth: 3375 feet

Operator License No.: 7383  
Op Name: GRADY BOLDING CORPORATION  
Address: PO BOX 486  
ELLINWOOD, KS 67526

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3347	2232	100 SX
SURF	8.625	561	0	275 SX <u>109.69</u>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/25/2008 3:00 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: GRADY BOLDING Company: GRADY BOLDING CORPORATION Phone: (620) 564-2240

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 500# hulls.

Plugging Proposal Received By: BRUCE RODIE WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 07/25/2008 6:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Bottom sanded with 5 sxs cement.  
Casing cut at 2232'.  
Pulled casing to 1500' - tied to casing - pumped 100 sxs cement with 300# hulls.  
Pulled to 850' - pumped 30 sxs cement with 100# hulls.  
Pulled to 600' - pumped 50 sxs cement with 100# hulls.  
Pulled to 150' - pumped 125 sxs cement - circulated to surface.  
Pulled casing - stayed full.

Perfs:

**INVOICED**  
DATE 8-6-08  
INV. NO. 2009060198

RECEIVED  
KANSAS CORPORATION COMMISSION

AUG 01 2008

CONSERVATION DIVISION  
WICHITA, KS

Remarks: COPELAND ACID AND CEMENTING-TICKET #35563.

Plugged through: CSG

District: 04

Signed Bruce Rodie  
(TECHNICIAN)

CM

Form CP-2/3

JUL 29 2008

ISERN-SCHULTZ OIL & GAS INC.

BOX 486  
ELLINWOOD, KS 67526

#3 "B" SELLENS

36-15-13W  
150' NE  
SE NW SE

CONTR WOODMAN & IANNITTI DRLG. CTY RUSSELL

GEOLOGICAL LEWIS CHUBB FIELD DOERR

E 1892 KB CM 9/26/79 <sup>CARD</sup> ISSUED 2/28/80 IP 5 BOPD & 2 1/2 BWPD  
ARB OH 3347-3375

+	+
+	+

API 15-167-21,350

SMP	TOPS	DEPTH	DATUM
ANH		835	+1057
TOP		2916	+1024
HEEB		2993	-1101
TOR		3010	-1118
BR LM		3078	-1186
LANS		3088	-1196
BKC		3325	-1433
ARB		3344	-1452
RTD		3350	-1458
DDTD		3375	-1483

8-5/8" 56/275sx, 5 1/2" 3347/100sx

NO DST'S  
MICT - CO, DD TO 3375 (ARB OH) 3344-  
3375, AC 1300 GAL, SWB 2 BOPH W/TR  
WTR, POP, 5 BOPD & 2 1/2 BWPD

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS