

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-195-22017-00-00  
Spot: W2NESW Sec/Twnshp/Rge: 22-15S-25W  
1865 feet from S Section Line, 3524 feet from E Section Line  
Lease Name: CARUSO D Well #: 1  
County: TREGO Total Vertical Depth: 4360 feet

Operator License No.: 5663  
Op Name: HESS OIL COMPANY  
Address: PO BOX 1009  
MCPHERSON, KS 67460

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4349	0	400 SX
SURF	8.625	210	0	150 SX

141-70

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/25/2008 11:30 AM  
Plug Co. License No.: 5663 Plug Co. Name: HESS OIL COMPANY  
Proposal Rcvd. from: ARNOLD HESS Company: HESS OIL COMPANY Phone: (785) 731-5615

Proposed Plugging Method: Ordered 400 sxs 60/40 pozmix - 4% gel - 500# hulls - 15 sxs gel spacer.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 07/25/2008 7:00 PM KCC Agent: MARVIN MILLS

**Actual Plugging Report:**

Ran tubing into 4326' - pumped 40 sxs 60/40 pozmix - 4% gel with 175# hulls.  
Pulled tubing to 3966' - pumped 15 sxs gel spacer.  
Pulled tubing to 1900' - pumped 220 sxs cement - good circulation of cement.  
Pulled tubing out - tied onto backside - pumped 115 sxs cement.  
Max. P.S.I. 425#. S.I.P. 225#.  
Pumped 25 sxs down top 5 1/2" full.

RECEIVED  
KANSAS CORPORATION COMMISSION  
  
JUL 31 2008  
  
CONSERVATION DIVISION  
WICHITA, KS

**Perfs:**

Top	Bot	Thru	Comments
4349	4360		

INVOICED


DATE 8-6-08  
INV. NO. 2009060199

Remarks: SWIFT SERVICES CEMENTING COMPANY-TICKET #14807.

Plugged through: TBG

District: 04

Signed \_\_\_\_\_



(TECHNICIAN)

CM

JUL 28 2008



HESS OIL COMPANY  
MOTHERSON, KS 67460

22-18-25W  
1665'FSL & 8524'FEL SEC

#3 GARISO 5D

CH 2-1/2" I.C. 2-1/2" W OF ARNOLD, KS  
BY: MALLARD JV, INC  
BY: JAMES G. HESS

BY: TREGO  
BY: WC (GOOD SCIENCE WEST  
DISE)

AS 18-185-22017

DATE 05/18/68 DATE 05/22/68 DATE 05/22/68 DATE 12/20/68 DATE 12/20/68


EV 2802 TO SHIP  
TOPS ..... Depth/datum  
SC ..... 1032 - 1050  
E/SC ..... 1070 - 1112  
HEE ..... 1696 - 1814  
LANS ..... 2786 - 1804  
STARIC ..... 2866 - 1898  
BKC ..... 4026 - 1644  
MARM ..... 4041 - 1656  
PAY ..... 4168 - 1776  
FT SC ..... 4234 - 1682  
CHER SH ..... 4264 - 1682  
MISS DOL ..... 4860 - 1696  
RTD ..... 4860 - 1676  
NO LOG

W STATUS  
OIL, F 1 EQ L 84 BWFD, MISS 4345 - 4377,  
NOTE CORRECTION: 12/20/68 - ORIG FR AS 1602'FSL &  
8600'FEL SEC  
GSG: E-3/8" 210 / 160 SX, E-1/2" 4345 / 400 SX  
NO CORES  
DST (1) 4266-4860 (FT SC), / 60-20-60-80, 65' GIP, REG  
E OIL 840' OSW (60% OIL) ISIP 10924' FSIP 10326'  
HT 1408' - 2016' HT 2886' - 2144' HT 2208' HT 2177'  
MIGT - 60, (MISS OIL), AG 300 GAL, 80, SET 2-3/8" TEG  
AT 4860, NO PKR. POP, F 1 EQ L 84 BWFD (CR 89),  
6/27/68 (MARM PAY REMAINS BEHIND PIPE)

COPYRIGHT 1968  
INDEPENDENT OIL & GAS SERVICE INC.  
WICHITA, KANSAS