

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-21004-00-01
Spot: W2SWNW Sec/Twnshp/Rge: 8-27S-12W
3240 feet from S Section Line, 5080 feet from E Section Line
Lease Name: POLLOCK OWWO Well #: 1
County: PRATT Total Vertical Depth: 4385 feet

Operator License No.: 31980
Op Name: LOTUS OPERATING COMPANY, L.L.C.
Address: 100 S MAIN STE 420
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2730		WITH 2 SX CMT
PROD	4.5	4384	2369	WITH 250 SX CMT 142.51
SURF	8.625	486		WITH 325 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/08/2008 10:30 AM
Plug Co. License No.: 7407 Plug Co. Name: EAGLE WELL SERVICE DBA BRONCO ENERGY SERVICES
Proposal Rcvd. from: ROBIN BROWN Company: LOTUS OPERATING Phone: (316) 262-1077

Proposed Plugging Method: CIBP @ 3670' WITH 2 SX CMT. PLUG AT 1000' WITH 12 SX GEL & 50 SX CMT. PLUG AT 520' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/11/2008 12:15 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

BOTTOM PLUG SET HIGHER THAN REQUESTED. AGENT FOR OPERATOR GOT #1 & #2 WELLS TURNED AROUND. SET CIBP @ 2730' & PUT 2 SX CMT ON TOP. 1ST PLUG AT 1000' WITH 12 SX GEL & 50 SX CMT. 2ND PLUG AT 500' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT. LOST CIRCULATION WHILE SPOTTING PLUG AT 60'. NO CMT TO SURFACE. LET CMT SET OVERNIGHT. WILL TAG TOC IN MORNING. 7/9/08: RAN TBG. TAG TOC @ 237'. FL @ 120'. 7/11/08: TOPPED 8 5/8" OFF FROM 120' TO SURFACE WITH 35 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4251	4256		
4200	4210		
3720	3776		

INVOICED

DATE 8-6-08
INV. NO. 2009060201

RECEIVED
KANSAS CORPORATION COMMISSION


JUL 28 2008

CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: TBG

District: 01



Signed

Stephen J. Pfeifer
(TECHNICIAN)