

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-25790-00-00
Spot: NWNE Sec/Twnshp/Rge: 27-14S-16W
330 feet from N Section Line, 840 feet from E Section Line
Lease Name: SCHRANT Well #: 3
County: ELLIS Total Vertical Depth: 3550 feet

Operator License No.: 30737
Op Name: YOST, M.A. OPERATIONS, INC
Address: 611 S FOSSILL PO BOX 811
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	985		

115.38

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 07/03/2008 12:00 PM
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING
Proposal Rcvd. from: TOM ALM Company: YOST, M.A. OPERATIONS, INC. Phone: (785) 483-6455

Proposed Plugging Method: Ordered 180 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: EDWIN SCHUMACHER WitnessType: NONE
Date/Time Plugging Completed: 07/03/2008 1:30 PM KCC Agent: EDWIN SCHUMACHER

Actual Plugging Report:

1st. Plug at 3370' w/25 sxs.
2nd. Plug at 1030' w/40 sxs.
3rd. Plug at 420' w/80 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.
Mousehole with 10 sxs.

Perfs:

INVOICED

DATE 8-6-08
INV. NO. 2009060202

RECEIVED
KANSAS CORPORATION COMMISSION

AUG 01 2008

CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed Ed Schumacher
(TECHNICIAN)

CM

Form CP-2/3

JUL 30 2008

PKS