

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

15-065-03015-00-00

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
4/19/66
APR 19 1966
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Tulsa Supply Company.

Complete Address: Box # 924, Tulsa, Oklahoma.

Lease Name Sturgeon Well No. 1

Location NE-NW-SE Sec. 32 Twp. 9 Rge. (E) (W) 22

County Graham Total Depth 3854

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Company.

Address: Box #405, Chase, Kansas. License No. 436

Operation Completed: Hour 1:00PM Day 16 Month 4 Year 1966

The Above well was plugged as follows:

203'--8 5/8" Surface pipe, cement circulated with ??
3854'--5 1/2" Production casing cemented with 100 Sx. Well plugged back to
3800'. Top perforations from 3786' to 3790'.

Sanded well back to 3770' and set 5 Sx. cement with dump bailer. Pulled
5 1/2" to 600' and attempted to circulate heavy gel mud. (Pumped in 13 Sx.
gel). Pulled 5 1/2" to 430' and pumped in 7 Sx. gel. No circulation. Pulled
5 1/2" to 366' and gel circulated. Displaced 20 Sx. cement thru 5 1/2" at 366'.
Pulled 5 1/2" to 206' and displaced 20 Sx. cement thru 5 1/2". Pulled 5 1/2", set
rock bridge @ 35' and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. Deibel
Well Plugging Supervisor

INVOICED

DATE 4/19/66
INV. NO. 3041-W