

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 126-33

LOCATION NE NE SW

SEC. 32 TWP. 9 RGE 22

Dry Hole  Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. 1 Lease Munert Mumert

Operator Colorado Oil & Gas Corp. Address Box 1030 Wichita, Kans

Field \_\_\_\_\_ County Graham

Total Depth 3840 Feet.

Plugging Contractor West Supply Co

Plugging Contractor's License No. 14

Address \_\_\_\_\_

(Describe briefly the manner in which the well was plugged)

8 5/8" at 215' circulated with cement - 5 1/2" at 3840.

P.B. to 3775', perforated at 3764'

Filled with sand to 3750', set 4 sax cement with dump bailer,

pulled 3680', 5 1/2" - filled hole with mud (35 sax Gel) to 210',

set rock and 20 sax cement, mud to 35', set rock and 10 sax

cement to bottom cellar.

**PLUGGING**  
FILE SEC 32 T. 9 R. 22W  
BOOK PAGE 126 LI E. 32

RECEIVED  
STATE CORPORATION COMMISSION  
1/23/57  
JAN 23 1957  
CONSERVATION DIVISION  
Wichita, Kansas

District Conservation Agent  
Date 1-18-57