

15-065-20456-00-00

Form CP-3  
Rev. 6-4-68

KANSAS

*Y*

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 21 1971  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Chief Drilling Company, Incorporated,

Complete Address 905 Century Plaza, Wichita, Kansas.

Lease Name Sturgeon Well No. 1

Location SW-NE-SE Sec. 32 Twp. 9 Rge. (E) (W)22

County Graham Total Depth 3810'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated     

Plugging Contractor Above

Address      License No.     

Operation Completed: Hour 9:00 AM Day 15 Month 6 Year 1971

The above well was plugged as follows:

253'--8 5/8" Surface casing, cement circulated with 175 Sx.  
Top of Dakota section @ 775'.

Circulated hole with heavy mud. Pulled DP to 1000' and displaced 100 Sx. cement thru  
DP from 1000' to 675'. Pulled DP to 275' and displaced 25 Sx. cement thru DP from  
275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *H. L. Nichols*  
Well Plugging Supervisor

INVOICED

DATE 6/22/71

INV. NO. 3888-W