

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. \_\_\_\_\_

LOCATION NE NE NW

SEC. 32 TWP. 9 RGE. 22 *w*

Dry Hole  Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 1 Lease Farrell 910 Union Nat'l Bldg Bldg.

Operator Murfin Drg Co Address Wichita, Kans

Field \_\_\_\_\_ County Graham

Total Depth 4035 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 162' circulated with cement - 5 1/2" at 4035' with  
100 sax cement behind - perforated at 3621' and squeezed with  
250 sax cement - perforated at 3786'.

Filled with sand and chat and Baker plugs to 3780', set 5  
sax cement with dump bailer, pulled 2909' 5 1/2", filled hole  
with mud - 50 sax Aquagel pumped in to 170', set cementing  
plug and 15 sax cement, mud to 35', set cementing plug  
and 10 sax cement to bottom cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
12/27/52  
DEC 27 1952

*Leon T. ...*  
District Conservation Agent

**PLUGGING**  
FILE SEC 32 T 9 R 22  
BOOK PAGE 68 LINE 37

CONSERVATION DIVISION  
Wichita, Kansas

Date 12-23-52