

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION SE SE NW

SEC. 32 TWP. 9 RGE. 22 W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Farrell

Operator K & E Drg ~~Co~~ INC. Address Wichita, Kans

Field _____ County Graham

Total Depth 3890 Feet.

Plugging Contractor West Supply Co

Plugging Contractor's License No. 14

Address _____

(Describe briefly the manner in which the well was plugged)

8 5/8" at 193' circulated with cement - 5 1/2" at 3887' with 125

sax cement behind - P.B. to 3850', perforated at 3776'.

Filled with sand to 3760', set 4 sax cement with dump bailer,

pulled 5 1/2" - filled with mud to 190', set rock and 15 sax cement,

mud to 35', set rock and 10 sax cement to bottom cellar.

District Conservation Agent

Date 12-20-56

PLUGGING
FILE SEC 32 T 9 R 22W
BOOK PAGE 128 LINE 226

RECEIVED
STATE CORPORATION COMMISSION
DEC 26 1956
CONSERVATION DIVISION
Wichita, Kansas