

KANSAS

*W* STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
6/30/72  
JUN 30 1972  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Dreiling Oil, Incorporated,  
Complete Address R. R. #2, Victoria, Kansas.  
Lease Name Farrell Well No. B-1  
Location NW-SE-NW Sec. 32 Twp. 9 Rge. (E) (W) 22  
County Graham Total Depth 3770'  
Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & AX         
Other well as hereafter indicated         
Plugging Contractor Above  
Address        License No.         
Operation Completed: Hour 3:30 PM Day 28 Month 6 Year 1972

The above well was plugged as follows:

193'--8 5/8" Surface casing, cement circulated.  
Circulated hole with heavy mud. Pulled-DP to 975' and displaced 100 Sx. cement thru  
DP. Pulled DP to 200' and displaced 25 Sx. cement thru DP. Pulled DP, set bridge @  
40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

**INVOICED**

Signed: *M. S. Dickels*  
Well Plugging Supervisor

DATE 6/30/72  
INV. NO. 5965-W