

15-065-03021-00-00

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
5/28/62
MAY 28 1962

CONSERVATION DIVISION
Wichita, Kansas

TO:
J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Graham

Location: SW SW SW Sec. 35 Twp. 9 Rge. _____ (E) _____ (W) 22

Name of Field: _____ Total Depth: 3933

I have this date completed supervision of plugging of:

Lease Name: Moore Well No. 1

Operator's Full Name: Leslie Oil Co

Complete Address: 542 Pet Bldg Wichita, Kansas

Plugging Contractor: Knight Casing Pulling

Address: Chase, Kansas License No. 436

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent?

Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 6PM Day 31 Month 5 Year 62

The above well was plugged as follows:

8 5/8" 240' circulated with cement - 5 1/2" 3920' with 100 sax cement.

Filled with sand to 3900', set 4 sax cement with dump bailer, pulled 1200'

5 1/2" to 500', circulated hole with heavy mud (23 sax Gel), displaced 20 sax

cement through 5 1/2" at 400', heavy mud to 180', displaced 20 sax cement

through 5 1/2", heavy mud to 35', set bridge and filled to bottom cellar

with cement.

Mudding and cementing by Knight Company Pump truck.

Signed: Leon Petty
Conservation Division Agent

Reviewed: Harold J. Wells
Field Supervisor

Remarks:

INVOICED
DATE 6/4/62
INV. NO. 5095-W