

R

Form CP-3  
Rev. 6-26-62

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

DEC 15 1964

12-15-64

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Morgenstern & Specter, Incorporated,

Complete Address: Box #661, Russell, Kansas.

Lease Name Desair Well No. 2

Location CNW-SE-SE Sec. 34 Twp. 9 Rge. (E) (W) 21

County Graham Total Depth 3877

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Knight Casing Pulling Company,

Address: Box #405, Chase, Kansas. License No. 436

Operation Completed: Hour 3:00PM Day 10 Month 12 Year 1964

The Above well was plugged as follows:

284'--8 5/8" Surface pipe cement circulated.  
3864'--5 1/2" Production casing cemented with 200 Sx. 5 1/2" squeezed in the  
Dakota Sands to surface.

Sanded well back to ~~3864~~ 3850' and set 5 Sx. cement with dump bailer.  
Found fluid level @ 2100'. Filled 5 1/2" to 550' with heavy rotary drilling  
mud. Set rock bridge and filled 5 1/2" to bottom of cellar with Redi-Mix.  
(Used 3 yards Redi-Mix).

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Nichols  
Well Plugging Supervisor

DATE 12-15-64

INV. NO. 347-W