

15-065-20432-00-00
~~02472-00-02~~

Form CP-3
Rev. 6-4-68

KANSAS

10
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

4/19/71

RECEIVED
STATE CORPORATION COMMISSION
APR 19 1971
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Dreiling Oil, Incorporated,
Complete Address R. R. #2, Victoria, Kansas.
Lease Name Kobler Well No. 1
Location NE-SE-SW Sec. 20 Twp. 8 Rge. (E) (W) 23
County Graham Total Depth 3855'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Dreiling Oil, Incorporated,
Address R. R. #2, Victoria, Kansas. License No.
Operation Completed: Hour 5:45 AM Day 16 Month 4 Year 1971

The above well was plugged as follows:

182'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 825'.

Circulated hole with heavy mud.; Pulled DP to 1050' and displaced 100 Sx. cement thru
DP from 1050' to 725'. Pulled DP to 215' and displaced 25 Sx. cement thru DP from
215' to 140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *W. L. Nichols*
Well Plugging Supervisor

INVOICED
DATE 4/20/71
INV. NO. 3569-11