

15-065-20195-00-00

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAR 5 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Leo J. Dreiling Oil Company,

Complete Address R. R. #2, Victoria, Kansas.

Lease Name Robinson Well No. 1

Location NW-NE-NW Sec. 34 Twp. 10 Rge. (E) (W) 23

County Graham Total Depth 3845'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Russ Casing Pulling, Incorporated,

Address Box #1082, Great Bend, Kansas. License No. 623

Operation Completed: Hour 10:00 AM Day 28 Month 2 Year 1973

The above well was plugged as follows:

187'--8 5/8" Surface casing, cement circulated.

3844'--4 1/2" Production casing cemented on bottom with top of cement @ 3185'. No plug back nor perforations indicated.

Sanded well back to 3790' and set 4 Sx. cement with dump bailer. Pulled 4 1/2" casing (2550') and squeezed well initially with 5 sacks hulls and 13 sacks gel and followed with 110 Cu. Ft. cement from 900' to 575' then 9 sacks gel from 575' to 225' and followed with 30 Cu. Ft. cement from 225' to 150' then 3 sacks gel from 150' to 30' and finally 10 Cu. Ft. cement from 30' to bottom of cellar. (Mudding and cementing operations by Allied Cementing Company, Inc.).

I hereby certify that the above well was plugged as herein stated.

Signed: *R. L. Nichols*
Well Plugging Supervisor

INVOICED
DATE 3/5/73
INV. NO. 9093-41