

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
JUN 20 1974
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Dreiling Oil, Inc.

Complete Address R. R. #2 Victoria, Kansas

Lease Name Robinson Well No. 2

Location SE SE NW Sec. 34 Twp. 10 Rge. (E) (W) 23

County Graham Total Depth 3796' 3840'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Co. Tools

Address _____ License No. _____

Operation Completed: Hour 1:15 P Day 18 Month 6 Year 1974

The above well was plugged as follows:

Total Depth 3796' 8 5/8 csg set at 159' cwc 125 sk.

4 1/2 csg set at 3839' cw 159 sk cmt.

4 1/2 csg perf. (3751)

Set 4 1/2 wood plug at 3100' -dumped 4 sk cmt W/dump bailer. (3070-3100)

Cutoff and recovered 2060' of 4 1/2 csg.

Pumped down 8 5/8 csg with 20 sk gel & water W/300 lbs hulls, -70 sk cmt, -10 sk

gel & water -released 8 5/8 plug and pumped 50 sk cmt by Sun Cementing Co.

PP 200 lbs. SIP 100 lbs.

I hereby certify that the above well was plugged as herein stated.

Signed: Geo. A. Massey
Well Plugging Supervisor

INVOICED

DATE 6/21/74

INV. NO. 9337-W