

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
OCT 12 1970
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Murfin, Executive and Kantor,

Complete Address 617 Union Center, Wichita, Kansas.

Lease Name Griffith Well No. 1

Location 50' NE of SW-SW-NW Sec. 30 Twp. 10 Rge. (E) (W)23

County Graham Total Depth 3804'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Murfin Drilling Company,

Address 617 Union Center, Wichita, Kansas. License No.

Operation Completed: Hour 5:00 PM Day 8 Month 10 Year 1970

The above well was plugged as follows:

263'--8 5/8" Surface casing, cement circulated with 175 Sx.
Top of Dakota section @ 800'.

Circulated hole with heavy mud. Pulled DP to 1070' and displaced 100 Sx. cement thru
DP from 1070' to 700'. Pulled DP to 270' and displaced 25 Sx. cement thru DP from
270' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Nichols
Well Plugging Supervisor

DATE 10-12-70

INV. NO. 2667-W