

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
NOV 9 1972
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Don E. Pratt,

Complete Address Box #370, Hays, Kansas.

Lease Name Charlie Griffith Well No. 1

Location NE NE NW 140' ECL & 140' FNL-NW/4 Sec. 30 Twp. 10 Rge. (E) (W) 23

County Graham Total Depth 3980'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Dreiling Oil, Incorporated,

Address R. R. #2, Victoria, Kansas. License No.

Operation Completed: Hour 8:00 PM Day 7 Month 11 Year 1972

The above well was plugged as follows:

213'--8 5/8" Surface casing, cement circulated with 165 Sx.
Top of Dakota section @ 825'.

Circulated hole with heavy mud. Pulled DP to 1050' and displaced 110 Cu. Ft. cement
thru DP from 1050' to 725'. Pulled DP to 215' and displaced 30 Cu. Ft. cement thru
DP from 215' to 140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: R. L. DeChalk
Well Plugging Supervisor

DATE 11/9/72
INV. NO. 6604-W