

CP-3

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 46-22

LOCATION SE SE NE

SEC. 26 TWP. 10 RGE. 23

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Klenk

Operator Davis Bros Address 14 E 3rd Tulsa, Okla

Field _____ County Graham

Total Depth 3890 Feet.

Plugging Contractor Barnes & Sons & Halliburton Co

Plugging Contractor's License No. 9

Address _____

(Describe Briefly the manner in which the well was plugged)

8 5/8" at 184' circulated with cement - 5 1/2" 3887' with 125 sax cement behind - P.B. to 3687' - perforated 3663'

Filled with sand to 3650', set 4 sax cement with dump bailer, pulled

3165' 5 1/2" to 1000', circulated hole with heavy mud at 1000' with (40 sax

Gel) - displaced 20 sax cement through 5 1/2" at 600', heavy mud to

170', displaced 20 sax cement through 5 1/2", heavy mud to 35' set

cementing plug and 10 sax cement to bottom cellar.

Mudding and cementing by Halliburton Co.

Edna Letty
District Conservation Agent

Date 9-26-57

9-30-57
9-3
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC. 26 T. 10 R. 23W
BOOK PAGE 46 LINE 22