

15-065-20494-00-00

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
NOV 8 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Don E. Pratt.

Complete Address Drawer #370, Hays, Kansas.

Lease Name Cook Well No. 2

Location SE SE NW
140' FSL & 140' FSL of NW/4 of Sec. 26 Twp. 10 Rge. (E) (W) 23

County Graham Total Depth 3808'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Dreiling Oil, Incorporated,

Address R. R. #2, Victoria, Kansas. License No.

Operation Completed: Hour 12:30 PM Day 4 Month 11 Year 1971

The above well was plugged as follows:

155'--8 5/8" Surface casing, cement circulated with 130 Sx.
Top of Dakota section @ 700'.

Circulated hole with heavy mud. Pulled DP to 925' and displaced 100 Sx. cement thru
DP from 925' to 600'. Pulled DP to 185' and displaced 25 Sx. cement thru DP from
185' to 110'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols
Well Plugging Supervisor

INVOICED
DATE 11-11-71
INV. NO. 4628-11