

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

AUG 8 1972

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Don Pratt,

Complete Address Box #370, Hays, Kansas. 67601

Lease Name Bill Klenk- Well No. 3

Location SW SW NW  
440' FSL & 440' FWL of NW/4 Sec. 19 Twp. 10 Rge. (E) (W) 23

County Graham Total Depth 3990'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Dreiling Oil, Incorporated,

Address R. R. #2, Victoria, Kansas. License No.       

Operation Completed: Hour 8:00 AM Day 5 Month 8 Year 1972

The above well was plugged as follows:

210'--8 5/8" Surface casing, cement circulated with 140 Sx.  
Top of Dakota section @ 850'.

Circulated hole with heavy mud. Pulled DP to 1075' and displaced 110 Cu. Ft. cement  
thru DP from 1075' to 750'. Pulled DP to 215' and displaced 30 Cu. Ft. cement thru  
DP from 215' to 140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.  
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. Nichols  
Well Plugging Supervisor

INVOICED  
DATE 8/8/72  
INV. NO. 0134-W