

15-065-20625-00-00

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
AUG 30 1973
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Don E. Pratt,
Complete Address P. O. Box #370, Hays, Kansas.
Lease Name Alma Klenk Well No. 1
Location 440' FEL & 440' FSL of SE/4 Sec. 19 Twp. 10 Rge. (E) (W) 23
County Graham Total Depth 3768'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Murfin Drilling Company,
Address 617 Union Center, Wichita, Kansas. License No.
Operation Completed: Hour 11:00 PM Day 27 Month 8 Year 1973

The above well was plugged as follows:

171'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 800'.

Circulated hole with heavy mud. Pulled DP to 1025' and displaced 110 Cu. Ft. cement
thru DP from 1025' to 700'. Pulled DP to 185' and displaced 30 Cu. Ft. cement thru
DP from 185' to 110'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 8/30/73INV. NO. 7861-40Signed: M. L. Nichols

Well Plugging Supervisor