

02859-00-00
15-065-02587-20-20
KCC
R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 39-39

LOCATION NW NE SE

SEC. 21 TWP. 8 RGE. 25

Dry Hole Abandoned Oil Well x Abandoned Gas Well

I have this date completed supervision of plugging of:

Well No. A-4 Lease & Schmied

Operator C. U. Bay Address Box 513 Chase, Kans

Field County Graham

Total Depth 3955
~~3912x~~ Feet.

Plugging Contractor West Supply Co

Plugging Contractor's License No. 14

Address

(Describe briefly the manner in which the well was plugged)

8 5/8" at 342' circulated with cement - 4 1/2" at 3955' with
100 sax cement behind.

Perforated at 3748. Filled with sand to 3730', set 3 sax cement
with dump bailer. pulled 4 1/2", filled with mud to 342'. set
rock and 15 sax cement, mud to 35'. set rock and 10 sax
cement to bottom cellar.

E. C. Bay
District Conservation Agent

Date 6-16-54

RECEIVED
STATE CORPORATION COMMISSION

JUN 18 1954

CONSERVATION DIVISION
Wichita, Kansas

6/18/54

PLUGGING
FILE SEC 21 T 8 R 25W
BOOK PAGE 39 LINE 39