

15-065-0039600-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION,

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Biting Building  
Wichita, Kansas

WELL PLUGGING RECORD

Graham County, Sec. 34 Twp. 10S Rge. (E) 23 (W)

Location as "NE/CNW&SWK" or footage from lines NW/4 NW/4 NW/4

Lease Owner Walters Drilling Co., et al

Lease Name Schultz Well No. 1

Office Address 510 Orpheum Building, Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed December 8, 19 54

Application for plugging filed (verbal) December 8, 19 54

Application for plugging approved (verbal) December 8, 19 54

Plugging commenced December 8, 19 54

Plugging completed December 8, 19 54

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation None Depth to top Bottom Total Depth of Well 3920 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
None		0	171.86	8 5/8"	171.86	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set bottom plug at 165' with heavy mud and 15 sacks cement and 1/2 sack Hulls

Set top plug at 40' with heavy mud and 15 sacks cement and 1/2 sack Hulls

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Walters Drilling Co.  
Address 510 Orpheum Building, Wichita 2, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

Russell I. Baker (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Russell I. Baker

510 Orpheum Building, Wichita 2, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 10th day of December, 19 54

March 10, 1956

Pauline Anderson  
Notary Public.



PLUGGING  
FILE SEC 34 T 10 R 23W  
BOOK PAGE 83 LINE 30

RECEIVED  
12-16-54  
DEC 16 1954  
CONSERVATION DIVISION  
Wichita, Kansas

SCHULTZ NO. 1

Location: NW NW NW Sec. 34-10S-23W Date Spudded: 11-26-54  
 Graham County, Kansas

Operator: Walters Drilling Co. Rotary Completion: 12-8-54

Contractor: Walters Drilling Co. Elevation: 2355 Gr  
 2358 DF  
 2360 KB

Surface Casing: 8 5/8" set at 171.86'  
 with 100 sacks cement  
 and 1 Cal. Chloride

Oil String: None. D & A

L O G

(Figures indicate bottom of formation)

Surface	0 to 171
Shale and Shells	880
Shale, Sand and Iron	925
Shale and Shells	1100
Shale, Shells and Sand	1400
Sand	1595
Shale and Shells	1870
Anhydrite	1915
Shale and Shells	2395
Lime and Shale	2495
Lime	2563
Lime and Shale	3650
Lime	3851
Lime and Shale	3920
Total Depth	3920

The undersigned, Russell I. Baker, hereby certifies that the above log is a true and correct log of the formations encountered in drilling the above noted well as reflected by the Daily Drilling Reports.

WALTERS DRILLING CO.

By Russell I. Baker

Subscribed and sworn to before me  
 this 10th day of December, 1954.

Rubie Anderson  
 Notary Public

My commission expires March 10, 1956

**PLUGGING**  
 FILE SEC 34 T 10 R 23W  
 BOOK PAGE 83 LINE 30

RECEIVED  
 STATE COMMISSION  
 12-16-54  
 DEPT. OF REVENUE  
 CONSTRUCTION DIVISION  
 WICHITA, KANSAS