


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Graham County. Sec. 36 Twp. 10 Rge. (E) 23 (W)
Location as "NE/CNW/SW" or footage from lines S W S W N W 1/4
Lease Owner Cave-Quillen Oil Co.
Lease Name McCall Well No. 1
Office Address 703 Petroleum Bldg. Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed Feb 23 1958
Application for plugging filed Feb 23 1958
Application for plugging approved Feb 23 1958
Plugging commenced Feb 23 1958
Plugging completed Feb 23 1958
Reason for abandonment of well or producing formation Dry

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3800 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	203	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy Rotary mud to 550 ft., set
plug and cemented with 25 sacks cement through drill pipe.
Mudded hole to 200 ft, set plug and 1/2 sack Hulls and
cemented with 15 sacks cement through drill pipe. Mudded
to 40 ft., set plug and 1/2 sack Hulls and 10 sacks
cement to bottom of Cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor H 30, Inc.
Address 709 Petroleum Bldg. Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick
L. C. Sponenberg (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L. C. Sponenberg
(Address) _____

SUBSCRIBED AND SWORN TO before me this 25 day of February 19 58

My commission expires February 13, 1960

W. Rose
Notary Public.

RECEIVED
STATE CORPORATION COMMISSION

PLUGGING
FILE SEC 36 T 10 R 23W
BOOK PAGE 86 LINE 16

FEB 28 1958

CONSERVATION

15-065-00529-00-00

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS


COMPANY **Cave-Quillen Oil Co.**

SEC. **36** T. **10** R. **23** W
LOC. **S W S W N W $\frac{1}{4}$**

FARM **McCall** NO. **1**

COUNTY **Graham**
KANSAS

TOTAL DEPTH **3800**
COMM. **2/12/58** COMP. **2/23/58**
SHOT OR TREATED
CONTRACTOR **H-30, Inc.**
ISSUED



CASING
20 10
15 8 **203**
12 6
13 5

ELEVATION **2297 K.B.**

PRODUCTION **D & A**

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand	30
Shale	203
Clay & Sand	270
Shale & Shells with sand stks.	790
Sand & Pyrite	885
Shale - Shells with Shallow sand streaks	1275
Dakota sand	1495
Shale	1505
Bottom Dakota Sand	1550
Shells & Shale & Red Bed	1797
Anhydrite	1841
Shale & Shells	2195
Shale with lime stks.	2380
Shale & Lime	3572
Kansas City Lime	3800

FORMATION TOPS:

Hiebner	3526
Toronto	3545
Lansing	3565
Base K.C.	3793
T.D.	3800

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

By *P. C. Spruick*

STATE OF KANSAS x
SS,

COUNTY OF SEDGWICK

Subscribed and sworn to before me, a notary public, in and for said County and State this 25 day of Feb. 1958.

Rose Turey
Notary Public

My Commission expires February 13, 1960

RECEIVED
STATE CORPORATION COMMISS

FEB 28 1958

CONSERVATION DIVISION
Wichita

PLUGGING
FILE SEC. 36 T. 10 R. 23 W
BOOK PAGE 86 LINE 16