

15-065-03217-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER Drilled in 1955

LEASE NAME Diebolt LKC Unit

WELL NUMBER 10-3

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

3630 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 29 TWP. 10 RGE. 23 (X) or (W)

LEASE OPERATOR Geneva Resources, Inc.

ADDRESS 50 California St., Ste. 930, San Francisco, CA 94111 COUNTY Graham

PHONE# (415) 291-9500 OPERATORS LICENSE NO. 30241

Date Well Completed 11/01/55

Character of Well Oil

Plugging Commenced 03/26/91

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 03/26/91

The plugging proposal was approved on March 26, 1991 (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? Unknown If not, is well log attached? Yes

Producing Formation LKC Depth to Top 3648' Bottom 3900' T.D. 3940'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
LKC	Oil	Surface	209	8-5/8"	209'	None
		Surface	3943	5-1/2"	3943'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Squeezed 5-1/2" casing with 375 sx of cement blend to a maximum of 800 psi. Blend consisted of 450 sx of 65/35 pozmix, 10% gel, and 700 lbs. hulls. Squeezed 8-5/8" casing with 75 sx of cement blend to a maximum of 300 psi.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Hallibuton Services, Inc. License No. 5287

Address P. O. Box 428, Hays, KS 67601

RECEIVED
STATE CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Geneva Resources, Inc.

MAY 06 1991

STATE OF California COUNTY OF San Francisco, ss.


Thomas G. Smith (Employee of Operator, Wichita, Kansas) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Thomas G. Smith
50 California Street, Suite 930
(Address) San Francisco, CA 94111

SUBSCRIBED AND SWORN TO before me this 1st day of May, 19 91

Julia A. Schneider
Notary Public

Commission Expires: March 28, 1995



DIEBOCK UNIT # 10-3

