

15-065-00447-05-20 ¹⁰⁰⁰

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

2/10/66

FEB 10 1966

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Empire Drilling Company,

Complete Address: 650 4th National Bank Building, Wichita, Kansas.

Lease Name Madden--Davis Well No. B-1

Location CE $\frac{1}{2}$ -NE-SE Sec. 17 Twp. 8 Rge. (E) (W) 25

County Graham Total Depth 3805'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Barnes & Sons Pipe Pulling Company,

Address: 1216 N. Lincoln, Russell, Kansas. License No. 9

Operation Completed: Hour 1:30PM Day 5 Month 2 Year 1966

The Above well was plugged as follows:

199'--8 5/8" Surface pipe, cement circulated with 125 Sx.
3797'--5 1/2" Production casing cemented with 75 Sx. Well plugged back to
3778'. Top perforations @ 3661'.

Sanded well back to 3645' and set 5 Sx. cement with dump bailer.

Squeezed well with 25 sacks gel followed with 100 Sx. cement. Pump-in
pressure 350#. FSIP 125#. It was agreed with Mr. White that a measuring
line would be run on the well after cement set and well to be filled to
bottom of cellar with cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. Nichols
Well Plugging Supervisor

DATE 2/10/66

INV. NO. 2404-W