

STATE OF KANSAS
STATE CORPORATION COMMISSION

15-065-02229-0000


KCCGPH

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Graham County, Sec. 21 Twp. 8 Rge. 25 (E) (W)

Location as "NE/CNW/SW" or footage from lines NE NE SW
Lease Owner National Cooperative Refinery Association
Lease Name Schmied Well No. 1
Office Address 820 Union National Bank Building
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed September 10, 1952
Application for plugging filed September 11, 1952
Application for plugging approved September 12, 1952
Plugging commenced October 29, 1952
Plugging completed October 29, 1952
Reason for abandonment of well or producing formation Non Productive



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Pettie
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3925' Feet
Show depth and thickness of all water, oil and gas formations. P. B. 3687'

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	202'	Cemented
				5 1/2"	3925'	2657

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set I-W Bridging Plug at 3765'. Plug back with rock and chat to 3709', dumped 3 sacks cement, filled up to 3687'. Mudded hole to 202', Set bridge, dumped 15 sacks cement. Mudded hole to 35', dumped 10 sacks cement on up to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION
NOV 11 1952
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor West Supply Company
Address Chase, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. Jean Helms
820 Union National Bank Building
(Address)

SUBSCRIBED AND SWORN TO before me this 10 day of November, 1952

My commission expires February 20, 1953

I. A. Lange
Notary Public.

PLUGGING
FILE SEC 21 T 8 R 25
BOOK PAGE 44 LINE 12

15-065-02229-0000

CONTRACTOR'S WELL LOG

COMPANY: National Cooperative Ref'y. Ass'n.
 CONTRACTOR: Musgrove Petroleum Corporation
 FARM: Schneid #1
 LOCATION: NE NE SW Section 21-8-25
 Graham County, Kansas
 COMMENCED: August 3, 1952
 COMPLETED: August 18, 1952

0	95	Sand
95	140	Sandy Shale
140	170	Clay & Shale
170	202	Shale & Shell
202	950	Shale
950	1010	Sand
1010	1190	Shale
1190	1225	Sand
1225	1250	Shale
1250	1365	Shale & Sand
1365	1410	Sand
1410	1450	Lime
1450	1625	Shale & Shell
1625	1850	Red Bed & Shale
1850	1880	Sand
1880	2000	Shale
2000	2015	Sand
2015	2105	Shale
2105	2160	Lime
2160	2620	Shale & Shells
2620	2875	Shale
2875	3020	Shale & Lime
3020	3120	Shale
3120	3192	Shale & Lime Streaks
3192	3460	Shale
3460	3694	Shale & Lime
3694	3730	Lime
3730	3766	Lime & Shale
3766	3868	Lime
3868	3925	Shale & Lime
	3925	Total Rotary Depth

Set 202' of 8-5/8" surface casing, cemented with 150 sacks.

Set 3959' of 5-1/2", cemented with 100 sacks.

STATE OF KANSAS }
 COUNTY OF SEDGWICK } SS:

I, GORDON L. KOELLING, do hereby certify that the above and foregoing is a true and correct copy of the log of Schneid #1, Section 22-8-25, Graham County, Kansas, as reflected by the files of the Musgrove Petroleum Corporation.

MUSGROVE PETROLEUM CORPORATION

By Gordon L. Koelling
 Secretary-Treasurer

PLUGGING
 FILE SEC 21 T 2 R 25 W
 MARK 44 LINE 12

Subscribed and sworn to before me, a Notary Public, within and for Sedgwick County, Kansas, this 26th day of August, 1952.

Adm. C. [Signature] RECEIVED

Notary Public. COMMISSION
 STATE OF KANSAS

SEP 12 1952

CONSERVATION DIVISION

My commission expires August 31, 1955.

7/12/52