

15-065-00962-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

Locate well correctly on above Section Plat

Graham County. Sec. 36 Twp. 9 Rge. (E) 21 (W)
Location as "NE/CNW/SW" or footage from lines. SW SE SE
Lease Owner D. G. Hansen
Lease Name Renner Well No. 1
Office Address Logan, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed June 15 19 57
Application for plugging filed June 15 19 57
Application for plugging approved June 15 19 57
Plugging commenced June 15 19 57
Plugging completed June 15 19 57
Reason for abandonment of well or producing formation Too low Structurally

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas
Producing formation Depth to top Bottom Total Depth of Well 3998 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	176'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud to 171'.
Set plug. Put in 1/2 sack of Hulls
and 15 sacks of cement. Filled with
Heavy mud up to 40'. Set plug.
Filled to top with 1/2 sack Hulls
and 10 sacks of cement.


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor C-G Drilling Co.
Address 107 Rule Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Jay H. Galloway (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jay H. Galloway
107 Rule Bldg.
(Address)

SUBSCRIBED AND SWORN TO before me this 19th day of June, 19 57



My commission expires May 20, 1959

RECEIVED
STATE CORPORATION COMMISSION

Notary Public.

PLUGGING
FILE SEC 36 T 9 R 21W
BOOK PAGE 21 LINE 14

JUN 21 1957
CONSERVATION DIVISION
Wichita, Kansas

6-21-57

CONTRACTOR'S WELL LOGOPERATOR D. G. HansenWELL NAME Renner #1LOCATION SW SE SE Sec. 36-9-21WRIG NO. 1COUNTY GrahamSTATE KansasCOMMENCEMENT DATE June 7, 1957COMPLETION DATE June 15, 1957LOG OF WELL

Elevation 2288' rotary bushing.

All measurements taken from the top of rotary bushing.

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
0	175	Surface Soil		
175	1100	Sand-Shale		
1100	1300	Shale-Sand		
1300	1545	Sand		
1545	1820	Red Bed		
1820	1860	Anhydrite		
1860	1880	Lime-Shale		
1880	2225	Lime-Shale		
2225	2580	Lime-Shale	0° - 2500	
2580	2725	Lime-Shale		
2725	2930	Lime-Shale	0° - 2750	
2930	3035	Lime-Shale	0° - 3000	
3035	3365	Lime-Shale	0° - 3250	
3365	3465	Lime-Shale		
3465	3590	Lime-Shale	0° - 3500	
3590	3685	Lime-Shale		
3680	3805	Lime-Shale	0° - 3750	
3805	3925	Lime-Shale		
3925	3998	Lime-Shale		

CASING LEFT IN HOLE AFTER COMPLETION

Ran 176' (9jts.) 8-5/8" OD Surface Casing

STATE OF KANSAS

COUNTY OF SEDGWICK

SS.

The undersigned hereby certifies that to the best of his knowledge and belief, the above facts are true and correct.

C-G DRILLING CO.

By Jay H. Galloway

Subscribed and sworn to before me this 19th day of June, 1957.

Vicky Jacobs
Vicky Jacobs, Notary Public

My commission expires:
May 20, 1959

PLUGGING			
FILE	36	9	21W
BOOK	PAGE	21	14

CONS.

621-57

28825

Remittance Blank No. _____

D. G. HANSEN, Contractor
LOGAN, KANSAS

Enclosed please find check 2500 for amount of
invoices as follows:

Date 6/20 1957

[illegible]

REMARKS:

Remedy #1 Plug fee

Yours truly,

D. G. HANSEN, Contractor

By

STATE OF KANSAS

15-065-00962-00-00

INVOICE

June 17, 19 57

To: D. G. Hansen
c/o C-G Drilling Company
107 Rule Building
Wichita, Kansas

STATE CORPORATION COMMISSION
CONSERVATION DIVISION

~~500 BITE~~ 211 N. BROADWAY
WICHITA, KANSAS

For: PLUGGING ASSESSMENT AS FOLLOWS:

Renner # 1
SW SE SE 36-9-21W
Graham County
File No. 21-14

\$ 25.00

NOTE: We also need a well plugging application, well log, and a well plugging record on this well to complete our file.

RECEIVED
JUN 20 1957
H. G. CUMMINGS

OK.
Ch # 182419
C-90
6-21-57
C.W.

RETURN THIS COPY WITH REMITTANCE

