


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

02859  
15-065-02587-00-00  
WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Graham County, Sec. 21 Twp. 8S Rge. (E) 25 (W)  
Location as "NE/CNW%SW%" or footage from lines NW NE SE  
Lease Owner C. U. Bay  
Lease Name Schmied 'A' Well No. 4  
Office Address Chase Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Oil Well  
Date well completed June 7 19 52  
Application for plugging filed June 4 19 54  
Application for plugging approved June 9 19 54  
Plugging commenced June 9 19 54  
Plugging completed June 15 19 54  
Reason for abandonment of well or producing formation Failure to produce in commercial quantity  
If a producing well is abandoned, date of last production May 19 54  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation Lansing KC Depth to top 3748 Bottom Total Depth of Well 3956 Feet  
Show depth and thickness of all water, oil and gas formations. 3905 PH

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	342'	none
				8 1/2"	3955'	1393'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with sand from 3905' to 3700' and ran 3 sacks of cement. Set a rock bridge from 350' to 340' and ran 15 sacks of cement, at 340'. Mudded hole to 50', set a 10' rock bridge and ran 10 sacks of cement to top. Plugging completed

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Co., Inc.  
Address Chase, Kansas

STATE OF Kansas, COUNTY OF Rice, ss.  
Glen E. Armour (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Glen E. Armour

(Address)



SUBSCRIBED AND SWORN to before me this 21 day of June, 19 54

Vincent O. Gray Notary Public

24-7366-S 3-53-20M

PLUGGING  
FILE SEC 21 T 8 R 25W  
BOOK PAGE 29 LINE 39

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 30 1954  
6/30/54  
CONSERVATION DIVISION  
Wichita, Kansas

COMPANY: C. U. BAY Rotary Drilling Commenced: 5-18-52  
 Denver, Colorado Rotary Drilling Completed: 5-20-52

LOCATION: SCHEID "A" #4  
 NW NE SE Section 21-6S-25W  
 Graham County, Kansas

CONTRACTOR: PICKRELL DRILLING COMPANY  
 Wichita, Kansas

CASING RECORD: 344' 8 5/8" 24 1/2" sals. casing set at 344' in a 12 1/2" hole, cemented  
 with 200 sacks cement. Cement circulated.

3957' (116 lbs.) 4" O.D. 9.50" casing set at 3957' in a 7 7/8" hole, cemented with 100 sacks cement.

LOG

(Figures indicate bottom formation - measurements from top rotary bushing.)

Sand & Sand Rock	30	Circulate for Samples at 3680'.
Shale	520	" " " " 3760'.
Shells	625	" " " " 3840'.
Shale	860	" " " " 3902'.
Sand	1560	" " " " 3922'.
Sand & Shale	2150	" " " " 3958'.
Anhydrite	2182	
Shale & Shells	2460	
Shale	2885	
Lime & Streaks of Pyrite	2920	
Shale	3465	Elope test at 3000' - 0° off.
Shale & Lime	3545	Slope test at 3958' - 0° off.
Shale	3618	SLM at 3958' - O.K.
Lime & Shale	3710	
Lime	3958 Rotary T.D.	

The undersigned, C. W. Sebitts, Attorney-in-fact of PICKRELL DRILLING COMPANY, hereby certifies in behalf of said company, that the above log is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By C. W. Sebitts  
Attorney-in-fact

STATE OF KANSAS )  
                          ) SS  
COUNTY OF SEDGWICK )

On the 16th day of June, 1952, before me the undersigned, a Notary Public in and for the County and State aforesaid personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of Pickrell Drilling Company to the foregoing instrument as its Attorney-in-fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above

written.

E. H. Zimmerman  
Notary Public

My commission expires January 28, 1953.

