


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Graham County, Sec. 26 Twp. 10S Rge. 23W (E) (W)

Location as "NE/CNW%SW%" or footage from lines SE SE N E  
Lease Owner Transit Corporation  
Lease Name Klenk Well No. 1  
Office Address 1516 Liberty Bank Bldg., Okla. City, Okla.  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed 9-8 19 57  
Application for plugging filed Sept. 24 19 57  
Application for plugging approved Sept. 24 19 57  
Plugging commenced Sept. 24 19 57  
Plugging completed Sept. 26 19 57  
Reason for abandonment of well or producing formation \_\_\_\_\_



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production No. Production 19 \_\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well \_\_\_\_\_ Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	184'	None
				5 1/2"	3,890'	3350'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Lane Wells plug set 3687' filled hole with sand to 3650'.  
Dumped 4 sacks cement at 3650' with dump bailer. Set plug at  
600' pumped down 20 sacks cement. Filled hole with mud to 170'  
set plug and pumped down 20 sacks cement. Filled hole to  
35' with mud installed rock bridge 35' to 25'. Cemented to  
bottom of cellar with 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Barnes & Sons Pipe Pulling Co.  
Address Russell, Kansas

STATE OF Oklahoma COUNTY OF Oklahoma, ss.  
S. F. BLAKE (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) S. F. Blake  
1516 Liberty Bank Building, Okla. City, Okla.  
(Address)

SUBSCRIBED AND SWORN TO before me this 10 day of October, 19 57  
Carol Bradshaw  
Notary Public.



PLUGGING  
FILE SEC 26 T. 10 R. 23 W  
BOOK PAGE 46 LINE 22

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 31 1957 10-31-57  
CONSERVATION DIVISION  
Wichita, Kansas

DRILLER'S WELL LOG

Transit Corporation - Klenk # 1 Well  
SE SE NE Sec. 26-10S-23W  
Graham County, Kansas

Total Depth : 3890'  
Commenced: 8-29-57  
Completed: 9-8-57

Elevation 2347' K.B.  
Casing 8 5/8" @ 184' with  
124 sacks of cement.  
Casing 5 1/2" @ 3887' with  
125 sacks of Cement

Formation	Depth	
	From	To
Surface Clay	0	15
Shale - Shells	15	105
Sand & Shells	105	140
Shale & Shells	140	315
Shale	315	565
Shale and Shells	565	1470
Sand	1470	1571
Shale	1571	1770
Shale - Shells	1770	1820
Iron Sand	1820	1865
Anhydrite	1865	1900
Shale	1900	2335
Shale - Lime	2335	2505
Lime - Shale St.	2505	2650
Lime	2650	2722
Lime & Shale	2722	3630
Lime	3630	3738
Lime & Shale	3738	3890 T.D.

Formation Tops:

Heebner 3581'  
Toronto 3601'  
Lansing 3617'  
Base of  
Kansas City 3841'  
Rotary T.D. 3890' in Marmaton

I hereby certify the foregoing to be a true and accurate Driller's Log  
of the formations encountered in the above well.

TRANSIT CORPORATION

By L. J. Klenk

Subscribed and sworn to before me this  
8th day of October, 1957

My commission expires: July 1, 1959

COMMISSION

Coral Bradshaw  
Notary Public

OCT 28 1957  
10-29-57  
DIVISION  
Kansas

PLUGGING  
FILE SEC. 26 T. 10 R. 23 W  
BOOK PAGE 46 LI 22