


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Graham County. Sec. 30 Twp. 10 Rge. 23 (E) (W)
Location as "NE/CNW/SW" or footage from lines NW/NW/NW
Lease Owner Musgrove Petroleum Corporation
Lease Name Dorman Well No. #1
Office Address W. 10th, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil well now dry
Date well completed Feb. 12, 1952
Application for plugging filed Yes Oct. 1, 1958
Application for plugging approved Yes Oct. 2, 1958
Plugging commenced 11-19 1958
Plugging completed 11-24 1958
Reason for abandonment of well or producing formation dry

If a producing well is abandoned, date of last production June 1958
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. A.D. Fabricius
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 1111 9 1/2 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	surface	
				5 1/2"		795'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Measured into T.D. 1111 9 1/2.
Plugging started 11-19-58. Finished 11-24-58.
Plugged off bottom, put in 5 ft. rock and dumped 5 sacks cement.
Worked and shot pipe. Shot 5 1/2" casing at 795'. Built rack and slide and layed down pipe. Mudded to 185'. Put in 10 ft. rock bridge and dumped 25 sacks cement. Mudded to 40'. Set rock bridge and mixed 10 sacks cement for cap on well. Well completed.

RECEIVED
STATE CORPORATION COMMISSION

DEC 1-1 1958

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor J.O. Forbes d/b/a Forbes Casing Pulling Co.
Address Box 221, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
J.O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J.O. Forbes
Box 221, Great Bend, Kans. (Address)

SUBSCRIBED AND SWORN TO before me this 5th day of December, 1958
Betty S. Edman Notary Public.
My commission expires November 8, 1960



PLUGGING
FILE SEC. 30 T. 10 R. 23W
BOOK PAGE 133 LINE 31

CONTRACTOR'S WELL LOG

COMPANY: Musgrove Petroleum Corporation
 CONTRACTOR: Musgrove Petroleum Corporation
 FARM: Dorman #1
 LOCATION: NW NW NW Section 30-10S-23W
 Graham County, Kansas
 COMMENCED: January 25, 1952
 COMPLETED: February 12, 1952

0	5	Cellar
5	10	Surface soil
10	70	Clay & sand
70	185	Clay, sand & shale
185	276	Shale
276	455	Sandy shale
455	485	Sand
485	990	Shale & shells
990	1365	Shale, sand & pyrite
1365	1530	Red rock, shale
1530	1800	Sand & shale
1800	2540	Shale & lime streaks
2540	2735	Shale
2735	2880	Shale & lime streaks
2880	3755	Shale & lime
3755	3934	Lime
3934	4030	Lime & shale
4030	4067	Shale & lime streaks
4067	4100	Shale & broken lime
4100	4208	Shale & lime
4208	4235	Shale & cherty lime
4235	4267	Shale
4267	4336	Shale & lime
4336	4347	Cherty lime
4347	4449	Lime & shale

Set 187' of 8-5/8" surface casing, cemented with 140 sacks.

Set 4083.84' of 5-1/2", cemented with 110 sacks.

STATE OF KANSAS)
) SS:
 COUNTY OF SEDGWICK)

I, GORDON L. KOELLING, do hereby certify that the above and foregoing is a true and correct copy of the log of Dorman #1, Section 30-10S-23W, Graham County, Kansas, as reflected by the files of the Musgrove Petroleum Corporation.

MUSGROVE PETROLEUM CORPORATION

By Gordon L. Koelling
 Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, within and for Sedgwick County, Kansas, this 14th day of April, 1952.



My commission expires July 9, 1952.

May Lu Loper
 Notary Public
 RECEIVED
 STATE CORPORATION COMMISSION

PLUGGING
 FILE SEC 30 T 10 R 23W
 BOOK PAGE 133 LINE 31

OCT 2 1958
 CONSERVATION DIVISION
 Wichita, Kansas