

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

DEC 15 1964
12-15-64
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Adminstrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Darrell Kelso of Knight Casing Pulling Co has this
date requested permission to plug the following described well:
Morgenstern & Specter
Mr. Kelso guarantees payment of the plugging fee.

Operator's full Name: Morgenstern & Specter, Incorporated,

Complete Address: Box #661, Russell, Kansas.

Lease Name: Desair Well No. 2

Location: CNW-SE-SE Sec. 34 Twp. 9 Rge. (E) (W) 21

County Graham Total Depth 3877 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Kelso was instructed to plug the well as follows:--

284'--8 5/8" Surface pipe, cement circulated.
3864'--5 1/2" Production casing cemented with 200 Sx.
5 1/2" squeezed in the Dakota Sands to surface.

Sand well back to 3850' and set 5 Sx. cement with dump bailer.
Find fluid level and ~~with~~ either bail to 550' and set rock
bridge or fill to 550' with heavy mud and set bridge then fill
to bottom of cellar with Redi-Mix.

Very truly yours,

H. L. Nichols
Conservation Division Agent