



ROBERT B. DOCKING Governor
DALE E. SAFFELS Chairman
JULES V. DOTY Commissioner
JAMES O. GREENLEAF Commissioner
RAYMOND B. HARVEY Secretary
JACK GLAVES Gen. Counsel

State Corporation Commission
CONSERVATION DIVISION
(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
10/23/68
OCT 23 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Don Hall of Lynch Casing Pulling Company has this date requested permission to plug the following described well:

Mr. Hall guarantees payment of the plugging fee.

Operator's full Name: Specter Pipe & Supply, Incorporated,

Complete Address: Box #169, Russell, Kansas.

Lease Name: Fury Well No. A-2

Location: NW-NW-NE Sec. 20 Twp. 9 Rge. (E)(W) 21

County: Graham Total Depth 3812011 Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Hall was instructed to plug the well as follows:

- 240'--8 5/8" Surface casing, cement circulated.
- 3805'--5 1/2" Production casing, cemented on bottom and squeezed from anhydrite to surface. No indication of plug back or perforations.
- Push plug to 3500', build sand bridge and set 5 Sx. cement with dump bailer.
- Push plug to 1100', build sand bridge to 1050' and fill 5 1/2" to bottom of cellar with 5 1/2 yards Redi-Mix cement.

Very truly yours,

D. L. Nichols
Conservation Division Agent