



20432
15-065-~~02432~~-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
APR 19 1971
CONSERVATION DIVISION
Wichita, Kansas

4/19/71

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Lyle Hicks of Dreiling Oil, Incorporated, has this date requested permission to plug the following described well:

Mr. Hicks guarantees payment of the plugging fee.

Operator's full Name: Dreiling Oil, Incorporated,

Complete Address: R. R. #2, Victoria, Kansas.

Lease Name: Kobler Well No. 1

Location: NE-SE-SW Sec. 20 Twp. 8 Rge. (E)(W) 23

County: Graham Total Depth 3855' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Hicks was instructed to plug the well as follows:

182'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota @ 825'.

Circulate hole with heavy mud. Pull DP to 1050' and displace 100 Sx.
cement thru DP. Pull DP to 215' and displace 25 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

W. L. Nichols

Conservation Division Agent