

State of Kansas



FORM - CP-2  
Rev. 6-26-62

JOHN ANDERSON, Jr. Governor  
WILLIAM L. MITCHELL, Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
ROBT. C. LONDERHOLM Gen. Counsel

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

APR 21 1964  
APR 21, 1964  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dear Sir:

Mr. Albert Unruh of Southwest Csg. Pulling Co. has this date requested permission to plug the following described well:  
Imperial Oil of Kans. Inc.,  
Mr. Unruh guarantees payment of the plugging fee.

Operator's full Name: Imperial Oil Of Kansas, Incorporated,  
Complete Address: Box # 97, WaKeeney, Kansas.  
Lease Name: Dreiling Well No. A-1  
Location: NW-NW-SW Sec. 29 Twp. 8 Rge. (E) (W) 22  
County Graham Total Depth 3641 Oil Well X  
Gas Well      Input Well      SWD Well X D & A      Lost Hole     

Mr. Unruh was instructed to plug the well as follows:

220' -- 8 5/8" Surface pipe, cement circulated with 175 Sx.  
3640' -- 5 1/2" cemented with 150 Sx. Top perforations 3252 to 3262.  
Sand well back to 3242' and set 5 Sx. cement with dump bailer.  
Pull 5 1/2" to 500', circulate heavy gel mud and displace 20 Sx.  
cement thru 5 1/2". Pull 5 1/2" to 210' and displace 20 Sx. cement  
thru 5 1/2". Pull 5 1/2", set bridge @ 30' and 10 Sx. cement to bottom  
of cellar.

Very truly yours,

*H. L. Nichols*