



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

RECEIVED
STATE CORPORATION COMMISSION
MAR 5 1973
CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Russ Sullivan of Russ Casing Pulling, Inc., has this date requested permission to plug the following described well:

Mr. Sullivan guarantees payment of the plugging fee.

Operator's full Name: Leo J. Dreiling Oil Company,

Complete Address: R. R. #2, Victoria, Kansas.

Lease Name: Robinson Well No. 1

Location: NW-NE-NW Sec. 34 Twp. 10 Rge. (E)(W) 23

County: Graham Total Depth 3845' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Sullivan was instructed to plug the well as follows:

187'--8 5/8" Surface casing, cement circulated.

3844'-4 1/2" Production casing cemented on bottom with top of cement @ 3185'. No plug back nor perforations indicated.

Sand well back to 3790' and set 4 Sx. cement with dump bailer. Pull 4 1/2" casing and squeeze well with 5 sacks hulls, 25 sacks gel and 150 Cu. Ft. cement, staged.

Very truly yours,

R. L. Nichols

Conservation Division Agent