

State of Kansas



FORM - CP-2  
Rev. 6-26-62

JOHN ANDERSON, Jr. Governor  
WILLIAM L. MITCHELL, Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
ROBT. C. LONDERHOLM Gen. Counsel

### State Corporation Commission

#### CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

#### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

**RECEIVED**  
STATE CORPORATION COMMISSION

FEB 28 1964

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dear Sir:

Mr. Duane Born of Chem-Tech Services, Inc. has this

date requested permission to plug the following described well:  
Morrison Producing Co.

Mr. Born guarantees payment of the plugging fee.

Operator's full Name: Morrison Producing Company,

Complete Address: Box #712, Eldorado, Kansas.

Lease Name: Cook Well No. 1

Location: CSW-NW Sec 26 Twp. 10 Rge. (E) (W) 23

County Graham Total Depth 3825 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Born was instructed to plug the well as follows:

222' --7" Surface pipe, cement circulated with 135 Sx.

Circulate hole with heavy mud, set plug @ 550' and 15 Sx. cement.

" " 210' with 1/4 sk. hulls & 15 Sx. cement.  
" " 40 with 1/2 Sk. hulls & 10 Sx. cement.

Very truly yours,

*H. A. Nichols*