



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
NOV 8 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Bill Draper of Dreiling Oil, Incorporated has this date requested permission to plug the following described well:

Mr. Draper guarantees payment of the plugging fee.

Operator's full Name: Don E. Pratt,

Complete Address: Drawer # 370, Hays, Kansas.

Lease Name: Cook Well No. 2

Location: 440' F&L & 440' F&L-NW/4 Sec. 26 Twp. 10 Rge. (E)(W) 23

County: Graham Total Depth 3808' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Draper was instructed to plug the well as follows:

155'--8 5/8" Surface casing, cement circulated with 130 Sx.
Top of Dakota section @ 700'.

Circulate hole with heavy mud. Pull DP to 925' and displace 100 Sx.
cement thru DP from 925' to 600'. Pull DP to 185' and displace 25 Sx.
cement thru DP from 185' to 110'. Pull DP, set bridge @ 40' with 1/2 sack
hulls and 10 Sx. cement to bottom of cellar.

Very truly yours,

W. L. Nichols
Conservation Division Agent