

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

179 KCC 013
15-~~191~~-20033-00-00

RECEIVED
AUG 14 1967
08-14-1967
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Bob Miller of L. J. Dreiling & Sons has this

date requested permission to plug the following described well:

Mr. Miller guarantees payment of the plugging fee.

Operator's full Name: Leo J. Dreiling Oil Company,

Complete Address: Victoria, Kansas,

Lease Name: Feldt Well No. 1

Location: NE-SW Sec. 1 Twp. 8 Rge. (E)(W) 30

County Sheridan Total Depth 4275 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Miller was instructed to plug the well as follows:

325' -- 8 5/8" Surface pipe, cement circulated with 175 Sx. Dakota section from 1800' to 1990'.

Circulate hole with heavy mud, Pull DP to 2010' and displace 100 Sx. cement thru DP. Pull DP to 330' and displace 20 Sx. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

Very truly yours,

K. L. Nichols
Conservation Division Agent