

State of Kansas

FORM - CP-2



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 North Market
 WICHITA, KANSAS

RECEIVED STATE CORPORATION COMMISSION

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

SEP 28 1964
 9-28-1964
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Bob Barnes of Barnes & Sons Pipe Pulling Co. has this date requested permission to plug the following described well:

Mr. Barnes guarantees payment of the plugging fee.

Operator's full Name: Empire Drilling Company,

Complete Address: 650 4th National Building, Wichita, Kansas.

Lease Name: Goff Well No. 1 2 KCCapB

Location: CN $\frac{1}{2}$ -NE-NW Sec. 10 Twp. 8 Rge. (E) (W) 24

County Graham Total Depth 3706 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Barnes was instructed to plug the well as follows:

150'--8 5/8" Surface pipe, cement circulated. 3705'--5 1/2" Production casing cemented with 75 Sx. Top perforations from 3591' to 3587'.

Sa nd well back to 3575 and set 5 Sx. cement with dump bailer. Pull 5 1/2" casing to 600' and circulate heavy gel mud. Pull 5 1/2" to 540' and displace 20 Sx. cement thru 5 1/2". Pull 5 1/2" to 150' and displace 20 Sx. cement thru 5 1/2". Pull 5 1/2" set btidge @ 35' and 10 Sx. cement to bottom of cellar.

Very truly yours,

N. L. Nichols
 Conservation Division Agent