

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Butler County, Sec. 2 Twp. 26SRge. 3E E/W
Location as "NE/CNW 1/4 SW 1/4" or footage from lines _____
NW SE SE

Lease Owner Kansas Petroleum, Inc.

Lease Name Siders Well No. 2

Office Address 500 Insurance Bldg-212 N. Market-Wichita

Character of Well (Completed as Oil, Gas or Dry Hole) KS
Dry Hole

Date Well completed 10-10 1976

Application for plugging filed 10-10 1976

Application for plugging approved 10-10 1976

Plugging commenced 10-10 1976

Plugging completed 10-10 1976

Reason for abandonment of well or producing formation _____
Dry Hole


If a producing well is abandoned, date of last production _____
19 _____

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ted E. Dewey

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 2750'

Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above
Section Plat

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	207'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

10-10-76 Mud to 220' plugged with 1/2 sacks of hulls and 20 sacks of cement.

10-10-76 Mud to 40' plugged with 1/2 sacks of hulls and 10 sacks of cement.

10-10-76 Plugged rathole with 2 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION
OCT 28 1976
10-28-76
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor White & Ellis Drilling, Inc.

Box 448 - El Dorado, Kansas 67042

STATE OF Kansas COUNTY OF Butler, ss.
Ernest Sifford (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Ernest Sifford

(Address) _____

SUBSCRIBED AND SWORN TO before me this 27th day of October, 1976

L. B. Auer
L. B. Auer Notary Public.

My commission expires _____



DRILLERS LOG

OPERATOR: Kansas Petroleum, Inc.; 500 Insurance Bldg.; 212 N. Market; Wichita,
 CONTRACTOR: **White & Ellis Drilling, Inc., Box 448, El Dorado, Kansas 67042** KS 67202

Lease Name Siders Well No. 2

Sec. 2 T. 26S R. 3E Spot NW SE SE

County Butler State Kansas Elevation _____

Casing Record:

Surface: 8 5/8" @ 207' with 135 Sxs. 3% CC

Production: _____ @ _____ with _____ Sxs.

Type Well: D & A Total Depth 2750' K.B.

Drilling Commenced: 10-5-76 Drilling Completed 10-10-76

Formation	From	To	Tops
Cellar	0	7	Mississippi 2705
Soil	7	12	
Lime & Shale	12	207	
Shale & Lime (Stks)	207	500	
Shale & Lime	500	2030	
Lime	2030	2150	
Lime & Shale (Stks)	2150	2355	
Lime & Shale	2355	2705	
Lime	2705	2750	

RECEIVED
 STATE CORPORATION COMMISSION
OCT 28 1976
 CONSERVATION DIVISION
 Wichita, Kansas

COMPLETION RECORD

Liner Record: Size _____ From _____ To _____

Cementing Record: _____ Sacks _____

Perforating Record:

Formation _____ Perforated Interval _____ Number Shots _____

Initial Production: _____

Electric Log _____ Type and Depths Covered _____