

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS, 67202

K.A.R.-82-3-117

API NUMBER 15-015-23,020-00-00

LEASE NAME Foulston "A"

WELL NUMBER 1

990 Ft. from S Section Line

4080 Ft. from E Section Line

SEC. 2 TWP. 26 RGE. 3 (E) (XXX)

COUNTY Butler

Date Well Completed 11-1-87

Plugging Commenced 9-18-97

Plugging Completed 9-19-97

TYPE OR PRINT
NOTICE: Fill out completely
and return to Coas. Div.
office within 30 days.

LEASE OPERATOR Range Oil Company, Inc.

ADDRESS 125 N. Market, Suite 1120 Wichita, Ks. 67202

PHONE (316) 265-6231 OPERATORS LICENSE NO. 5120

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)

by _____ (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Mississippian Depth to Top 2,687 Bottom _____ T.D. 2,750

Show depth and thickness of all water, oil and gas formations.

acid
10-3-97

OIL, GAS OR WATER RECORDS

CASING RECORD

10-3-97

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	208'	
				4 1/2"	2749'	2030'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to _____ feet each set. Sanded to 2648'. Bailed 4 sks cement. Shot at 2168' and 2030'. Jacked 3 joints. Pulled to 270'. Circulated 105 sks cement to surface. Pulled the rest of the pipe. Hole stayed full.

Topped off with 20 sks cement.

Name of Plugging Contractor Quality Well Service, Inc. License No. 31925

Address 249 E. Beth Drive Sterling, Ks. 67579

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Range Oil Company, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.


John M. Washburn

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) John M. Washburn

(Address) 125 N Market Suite 1120 Wichita, KS 67202



Subscribed and sworn to before me this 2nd day of October, 1997

Barbara J. Schmidt

Notary Public

Barbara J. Schmidt

My Commission Expires: July 13, 2001

USE ONLY ONE SIDE OF EACH FORM

GREAT GUNS

LOGGING

DIGITAL LOG

DUAL INDUCTION

LOG

15-015-23020

COMPANY: RANGE OIL CO. INC.
WELL: FOULSTON "A" #1
FIELD:
COUNTY: BUTLER

FILE NO.: 1387

STATE: KANSAS
COUNTRY: U.S.A.

LOCATION: 990'FSL&1200'FUL-SW

SEC: 2 TWP: 26S RGE: 3E

DATE: 10/13/87

RUN NO.: 1

PERMANENT DATUM: GL
DRILLING MEASURED FROM: KB
LOG MEASURED FROM: KB
ABOVE PERMANENT DATUM: 5.0

DEPTH--DRILLER: 2750.0
DEPTH--LOGGER: 2751.0
BOTTOM LOG INTERVAL: 2750.0
TOP LOG INTERVAL: 180.0

CASING DEPTH--DRILLER: 208.0
CASING DEPTH--LOGGER: 208.0
CASING DIAMETER: 8.625
BIT SIZE: 7.875

UNIT NO.: 62
LOCATION: MED. LDGE
RECORDED BY: G. STELTING
WITNESSED BY: MR. TIM LAUER

ELEVATIONS:

KB: 1289.0

DF: 1287.0

GL: 1284.0

SERVICES:

GR10

BCN

DENS

DINL

SOFTWARE VERSION:

401